

**COBB COUNTY
DEPARTMENT OF TRANSPORTATION
ENGINEERING DIVISION**

**Paper Mill Road School Zone
Sope Creek Elementary School
Project No. E6110
April 9, 2012**

ADDENDUM NO. 1

Proposals Received Until April 12, 2012 – 12:00 Noon Local Time

The following addendum hereby amends and/or modifies the Bid Documents and Contract Specifications as issued for this project. All bidders are subject to the provisions of this Addendum. **Bidders shall acknowledge receipt of this addendum and must use the attached revised bid schedule of items stamped Addendum No. 1.**

I. PREBID CONFERENCE

Minutes of the Prebid Conference held on Monday, April 2, 2012, are attached.

NOTE: Addenda, including plan holder lists, will be posted online at the following websites for Cobb Purchasing and Cobb DOT: <http://purchasing.cobbcountyga.gov/bid-list.htm> and <http://dot.cobbcountyga.gov/bid-rfp.htm>. Receipt of addenda must be acknowledged in the bid document. It is the bidder's ultimate responsibility to ensure that they have all applicable addenda prior to bid submittal and to utilize the latest bid schedule.

In an effort to meet Title VI requirements, contractors are encouraged to fill out the form in the bid package. This is strictly voluntary. Please place form in a separate envelope and deliver to Cobb County Purchasing Department.

II. QUESTIONS/ANSWERS

- Q. There is no pay item for convert existing catch basin to a manhole. Is this to be included in grading complete?
- A. See revised bid schedule.
- Q. There is no pay item for new structure A-2 (new drop inlet)?
- A. Included in pay item 668-2100.
- Q. Are the stumps of trees cleared by others going to be removed prior to construction?
- A. Stumps shall be removed by the Contractor during construction of this project.

ADDENDUM No. 1
April 9, 2012
Paper Mill Road School Zone
Sope Creek Elementary School
Project No. E8040
Page 2

II. QUESTIONS/ANSWERS (continued)

Q. There are two line items in bid schedule for retaining wall, "Line item #35 -30 CY Class A Concrete, Incl reinf steel for R Wall #1 and Line Item # 155 – 80 CY Class A concrete for Sdwk & R wall incl reinf steel", while plan reflected only one sidewalk turn up wall @ STA 48+00, 36.46' RT. Please provide proposed location for retaining wall # 1. We also do not found the profiles (Wall envelope) for any wall. Please provide profiles for both walls.

A. **Please see revised bid schedule. There is only one wall on this project.**

Q. There are one label "BY OTHERS BEGIN MILLING AND OVERLAY STA 45+18.37" on drawing no. 13-01. Plan does not reflected perimeter of that work. We assume that only overlay for School driveway is included in contract while milling and overlay for Paper mill road including proposed turn lane is not part of this contract. Please clarify, is it right?

A. **Yes.**

Q. Wall envelope and specs do not provided in plan and document. Please provide wall envelope (Profile) and specs on what type of finish does this turn up sidewalk wall receive at STA 48+00?

A. **Please see cross-sections. Ashlar finish.**

III. BID SCHEDULE

DELETED:

Pay Item #500-3800, Class A Concrete, Incl Reinf Steel, **0 CY**

Pay Item #611-8000, Adjust Catch Basin to Grade, **1 EA**

ADDED:


Pay Item #611-3005, Reconstruct Catch Basin to Junction Box, **1 EA**

REVISED:

Pay Item #500-3904, Class A Conc for SDWK & Ret. Wall Incl Reinf Steel, **30CY**

Questions should be sent via email, **no later than 2:00 p.m. on Monday, April 9, 2012**, to purchasing@cobbcounty.org

ADDENDUM No. 1
April 9, 2012
Paper Mill Road School Zone
Sope Creek Elementary School
Project No. E8040
Page 3



Michael C. Cates, P.E.
Pre-Construction Engineer

MSC/RJG/jan

cc: *Electronic copies:*

Cobb County Purchasing (w/hard copy)

Bob Galante, CCDOT Construction

Brook Martin, CCDOT Operations

Russell Cooke, CCWS

Wade Kelly, CCDOT Construction

Joe Alexander, CCDOT Construction

Jeff Neiswender, CCDOT Construction

Andy Rikard, CCDOT Utility Coordinator, Engineering

Donna Camp, CCDOT Construction

Bryan Ricks, CCDOT, Engineering

Kristen Orton, CCDOT Engineering

Lynn Lambert, CCDOT Engineering

Dyan Merced, CCDOT Engineering

David Muller, CCDOT Utility Coordinator, Construction

Attachment: Prebid Minutes & Revised Bid Schedule

**Paper Mill Road School Zone
Sope Creek Elementary School
Project No. E8040
PREBID CONFERENCE
Bid Date: April 12, 2012 – 12:00 Noon Local Time**

DATE: April 2, 2012

ATTENDEES: See Attached Sign-in Sheet

MEETING MINUTES:

- (1) This is the Prebid Conference for Cobb DOT PROJECT NO. E8040, Paper Mill Road School Zone/Sope Creek Elementary School, Bids will be received until 12:00 noon on April 12, 2012, at Cobb County Purchasing Department, 1772 County Services Parkway, Marietta, Georgia. Bids will be opened and read aloud at 2:00 p.m. at the Cobb County Purchasing Department, 1772 County Services Parkway.

NO BIDS WILL BE ACCEPTED AFTER THE 12:00 NOON DEADLINE. Those received late will be unopened. All bidders must be on record with Cobb County as having purchased plans and specifications. All bids shall be submitted on the Bid Proposal Form. Any revisions made on the outside of the envelope will not be accepted.

Addenda, including plan holder lists, will be posted online at the following websites for Cobb Purchasing and Cobb DOT: <http://purchasing.cobbcountyga.gov/bid-list.htm> and <http://dot.cobbcountyga.gov/bid-rfp.htm>. Receipt of addenda must be acknowledged in the bid document. It is the bidder's ultimate responsibility to ensure that they have all applicable addenda prior to bid submittal and to utilize the latest bid schedule.

Proposals may be rejected if any of the Unit Prices are obviously unbalanced. The County will decide whether any Unit Prices are unbalanced either excessively above or below a reasonable cost analysis value determined by the Engineer, particularly if these unbalanced amounts are substantial and contrary to the interest on the County.

DO NOT DELIVER BIDS TO COBB DEPARTMENT OF TRANSPORTATION.

The completion date for this project is 90 consecutive calendar days after issuance of the Notice to Proceed.

Minutes of this meeting and any revisions will be issued as Addendum No. 1.

- (2) **Introduction of Special Representatives in attendance.**
- (3) **Project Description:**

Project consists of adding a 100' decel lane with a 75' foot taper into Sope Creek Elementary School. Paper Mill Road will be resurfaced and restriped to accommodate a two way left turn lane from Old Paper Mill Road to Westbury Park Drive. Sope Creek Elementary School driveway will be widened to accommodate a left turn lane.

Payment will be made monthly based on approved invoices.

Cobb County Water System work is involved on this project. Only contractors or sub-contractors who have been prequalified with Cobb County Water System are allowed to perform water and sewer relocation work associated with this project. Bidders or their water/sewer subcontractor are required to have a State of Georgia Utility Contractor License.

**PREBID CONFERENCE
MEETING MINUTES
Paper Mill Road School Zone
Sope Creek Elementary School
Project No. E8040
April 12, 2012
Page 2**

(4) Bid Proposal and Contract Documents:

A Notice of Intent is not required on this project.

The **Contractor** must meet the current bid requirements of the Georgia Department of Transportation.

For all bids for contracts involving utility work as defined in O.C.G.A. 43-14-1 et.seq., the Contractor and/or its subcontractor(s) that will perform utility work must have a valid State of Georgia Utility Contractor License and comply with all applicable provisions of Chapter 14 of Title 43 of O.C.G.A.

The **Contractor** and their subcontractors are required to be in compliance with the "Georgia Security and Immigration Compliance Act." The Contractor must execute and submit at the time of the bid the "Contractor Affidavit and Agreement," (Page 1.15) or bid will be determined non-responsive and will be disqualified.

The **Contractor** must submit a DBE participation report to the **County** prior to beginning work on the project. A monthly DBE utilization report must be submitted with each monthly invoice. A final DBE report must be submitted at the end of the project. If DBE participation changes during the course of the project, an updated participation report must be submitted to the **County** at the time of such change. The County strongly supports DBE participation in all contracts.

DBE firms must be certified with the Georgia Department of Transportation's Equal Employment Opportunity (EE0) office.

(5) Utility Issues:

Contractor shall submit monthly reports of utility coordination correspondence.

It is the Contractor's responsibility to coordinate all utility relocations.

Utility delays due to lack of coordination on behalf of the contractor will not be considered for reprieve from liquidated damages.

This project is considered by the UPC to be a small ticket item.

(6) Right-of-Way:

All Parcels have been acquired.

**PREBID CONFERENCE
MEETING MINUTES
Paper Mill Road School Zone
Sope Creek Elementary School
Project No. E8040
April 12, 2012
Page 3**

(7) Special Items to Note:

All walls shall have an ashlar finish with anti-graffiti coating, cost to be included in price of concrete.

All storm drain shall be R.C.P., side drain pipe may be per GDOT selection chart.

If required the Contractor shall take three-point levels on Widening and Reconstruction Projects and obtain the Engineer's approval of the "best fit" profile and cross slope, to minimize leveling requirements of the existing roadway. The Contractor must get the Engineer's approval of the proposed best fit before beginning widening and reconstruction. This will also apply to all walls, contractor shall layout walls before constructing them to get Engineers approval.

Grass shall be replaced in kind to match existing prior to construction. Sod shall be replaced with sod, seeded grass shall be replaced with seed. There is a pay item for sod to be used in yards and beauty strip.

Trees outside of construction limits are to be removed only as directed by the Engineer.

Contractor will be required to mow grass no less than once a month until final acceptance.


(8) Review:

Section 150 Traffic Control

Section 150.08 Enforcement

(9) Questions and Answers:

- (10)** Questions should be sent via email, **no later than 2:00 p.m. on Monday, April 9, 2012**, to purchasing@cobbcounty.org



Michael S. Cates, P.E.
Pre-Construction Engineer

MSC/RJG/jan

COBB COUNTY DEPARTMENT OF TRANSPORTATION

PAPER MILL ROAD SCHOOL ZONE

SOPE CREEK ELEMENTARY SCHOOL

PROJECT NO. E8040

Pre-Bid Conference

April 2, 2012 10:30 a.m.

NAME	FIRM	OFFICE PHONE/FAX	EMAIL ADDRESS
Bill Thomas	CC Purchasing	O	
		F	
Kristen Orton	CCDOT	O	Kristen.orton@cobbcountry.org
		F	
SCOTT BEAUMONT	CHATFIELD CONTRACTING, INC.	O 770-514-9519	scott@chatfieldcontracting.com
		F 770-514-9648	
David Graham	Cobb DOT	O 770-528-3664	dgraham@cobbcountry.org
		F	
Andy Rickard	Cobb DOT / Arcadis	O 770-528-3660	andy.rickard@cobbcountry.org
		F	
DAVID MYVLEL	Cobb DOT / BECAINS UTILITIES	O 770-528-1651	DAVID.MYVLEL@COBBDOT.ORG
		FM 404-516-4441	

COBB COUNTY DEPARTMENT OF TRANSPORTATION

PAPER MILL ROAD SCHOOL ZONE

SOPE CREEK ELEMENTARY SCHOOL

PROJECT NO. E8040

Pre-Bid Conference

April 2, 2012 10:30 a.m.

NAME	FIRM	OFFICE PHONE/FAX	EMAIL ADDRESS
Cam Wade	Blount Construction	O 770-541-7333	cwade@blountconstruction.com
		F 770-541-7340	
Sio H. Jordan	CCDOT/Engineering	O 770-528-3685	sio.H.jordan@ CobbCountyGa.gov
		F	
JOE ALEXANDER	CCDOT/Atkins	O 770-528-1663	joe.alexander@CobbCountyGa.gov
		F	
Deb Paces	CCDOT	O	
		F	
Donna Camp	CCDOT/Arcadis	O 770-528-1642	donna.camp@CobbCountyGa.gov
		F 770-528-2129	
		O	
		F	

Cobb County Program Management Information System

Department of Transportation

Bid Schedule of Items - Project Detail

4/10/2012 10:16:26AM

Page 1 of 7

Contract No: C 000543

Vendor: _____

Project No: E804 SOPE CREEK ELEMENTARY PAPER MILL ROAD

Signature: _____

Group:MSC MISCELLANEOUS

Line No.	Approx Quant.	Item	Unit Price	Amount
5	1.00 LS	205-0100 CONSTRUCTION ALLOWANCE	FIXED	\$75,000.00
10	8.00 EA	634-1201 RIGHT OF WAY, PROPERTY LINE IRON PIN		
15	2.00 EA	999-3015 SPLOST SIGN INSTALLATION, HARDWARE, POSTS	\$100.00	\$200.00
20	2.00 EA	999-3025 PEACH ROAD SIGN INSTALLATION, HARDWARE/POST	\$100.00	\$200.00
TOTAL			MISCELLANEOUS	

Cobb County Program Management Information System

Department of Transportation

Bid Schedule of Items - Project Detail

4/10/2012 10:24:34AM

Page 2 of 7

Contract No: C 000543

Vendor: _____

Project No: E804 SOPE CREEK ELEMENTARY PAPER MILL ROAD

Signature: _____

Group:R01 RETAINING WALL NO. 1

Line No.	Approx Quant.	Item	Unit Price	Amount
25	10.00 CY	205-0074 EXCAVATION - UNDERCUT		
30	10.00 CY	207-0203 FOUND BK FILL MATL, TP II		
TOTAL			RETAINING WALL NO. 1	

Cobb County Program Management Information System

Department of Transportation

Bid Schedule of Items - Project Detail

4/10/2012 10:24:34AM

Page 3 of 7

Contract No: C 000543

Vendor: _____

Project No: E804 SOPE CREEK ELEMENTARY PAPER MILL ROAD

Signature: _____

Group:T01 ROADWAY

Line No.	Approx Quant.	Item	Unit Price	Amount
35	1.00 LS	150-1000 TRAFFIC CONTROL		
40	1.00 ACR	163-0232 TEMPORARY GRASSING		
45	15.00 TON	163-0240 MULCH		
50	1.00 EA	163-0300 CONSTRUCTION EXIT		
55	100.00 EA	163-0550 CONSTRUCT & REMOVE INLET SEDIMENT TRAPS		
60	50.00 LF	165-0030 MAINTENANCE OF TEMPORARY SILT FENCE - TP C		
65	1.00 EA	165-0101A MAINTENANCE OF CONSTRUCTION EXIT		
70	100.00 EA	165-0105 MAINTENANCE OF INLET SEDIMENT TRAPS		
75	100.00 LF	171-0030 TEMPORARY SILT FENCE, TYPE C		
80	1.00 LS	210-0100 GRADING COMPLETE		
85	1,450.00 SY	310-5100 GR AGGR BASE CRS, 10 INCH, INCL MATL		
90	15.00 TON	402-1802 RECYCLED ASPH CONC PATCHING INCL BIT MATL & H LIME		
95	15.00 TON	402-1812 RECYCLED ASPH CONC LEVELING,INCL BIT MAT & HYD LIM		

Cobb County Program Management Information System

Department of Transportation

Bid Schedule of Items - Project Detail

4/10/2012 10:24:34AM

Page 4 of 7

Contract No: C 000543

Vendor: _____

Project No: E804 SOPE CREEK ELEMENTARY PAPER MILL ROAD

Signature: _____

Group:T01 ROADWAY

Line No.	Approx Quant.	Item	Unit Price	Amount
100	810.00 SY	402-3910 RECYC 1.5" ASP CON 12.5MM SPRPPAVE GP2 INC BM & HL		
105	1,300.00 SY	402-4012 RECYC 2" ASP CON 19MM SPRPAVE GP1 OR 2 INC BM & HL		
110	1,300.00 SY	402-4310 RECYC 4" ASPH CONC 25MM SPRPAVE GP1OR 2 INCL BM&HL		
115	225.00 GAL	413-1000 BITUM TACK COAT		
120	345.00 SY	432-5010 MILL ASPHALT CONC PVMT, VARIABLE DEPTH		
125	85.00 SY	441-0104 CONC SIDEWALK, 4 IN		
130	1.00 EA	441-1012 CURB CUT WHEELCHAIR RAMPS TP B		
135	675.00 LF	441-6216 CONC CURB & GUTTER, 8 IN X 24 IN, TP 2		
140	2,500.00 LF	446-1002 PVMT REINF FABRIC STRIPS, TP 2, INCL BITUM BINDER		
145	5.00 CY	500-3205 CLASS B ROAD WIDENING CONCRETE		
150	30.00 CY	500-3904 CLASS A CONC FOR SDWK & RET. WALL INCL REINF STEEL		
155	15.00 LF	550-1180 STORM DRAIN PIPE, 18 IN, H 1-10		
160	1.00 EA	611-3005 RECONSTR CATCH BASIN TO JUNCTION BOX		

Cobb County Program Management Information System

Department of Transportation

Bid Schedule of Items - Project Detail

4/10/2012 10:24:34AM

Page 5 of 7

Contract No: C 000543

Vendor: _____

Project No: E804 SOPE CREEK ELEMENTARY PAPER MILL ROAD

Signature: _____

Group: T01 ROADWAY

Line No.	Approx Quant.	Item	Unit Price	Amount
165	300.00 LF	615-1200 DIRECTIONAL BORE Desc: 7 INCH		
170	58.00 SF	636-1020 HWY SIGNS, TP 1 MATL-REFL SHEETING, TP 3		
175	84.00 LF	636-2005 PAINTED "U" CHANNEL POST, TP 3		
180	1.00 EA	639-3004 STEEL STRAIN POLE, TP IV Desc: W/35 FT MAST ARM (FOR FOUNDATION & INSTALL O		
185	1.00 EA	639-3004 STEEL STRAIN POLE, TP IV Desc: W/50 FT MAST ARM (FOR FOUNDATION & INSTALL O		
190	1.00 EA	639-3004 STEEL STRAIN POLE, TP IV Desc: W/60 FT MAST ARM (FOR FOUNDATION & INSTALL O		
195	100.00 LF	643-3000 ORANGE SAFETY FENCE		
200	1.00 LS	647-1000 TRAFFIC SIGNAL INSTALLATION		
205	7.00 EA	653-0120 THERMOPLASTIC PVM T MARKING, ARROW, TP 2		
210	2.00 EA	653-0130 THERMOPLASTIC PVM T MARKING, ARROW, TP 3		
215	170.00 LF	653-1501 THERMOPLASTIC SOLID TRAFFC STRIPE, 5 IN,WHITE		
220	250.00 LF	653-1502 THERMOPLASTIC SOLID TRAFFC STRIPE, 5 IN,YELLOW		

Cobb County Program Management Information System

Department of Transportation

Bid Schedule of Items - Project Detail

4/10/2012 10:24:34AM

Page 6 of 7

Contract No: C 000543

Vendor: _____

Project No: E804 SOPE CREEK ELEMENTARY PAPER MILL ROAD

Signature: _____

Group:T01 ROADWAY

Line No.	Approx Quant.	Item	Unit Price	Amount
225	59.00 LF	653-1704 THERMOPLASTIC SOLID TRAFFIC STRIPE, 24 IN, WHITE		
230	610.00 LF	653-1804 THERMOPLASTIC SOLID TRAFFIC STRIPE, 8 IN, WHITE		
235	140.00 SY	653-6004 THERMOPLASTIC TRAF STRIPING, WHITE		
240	1.00 EA	668-2100 DROP INLET, GP 1		
245	1.00 ACR	700-6910 PERMANENT GRASSING		
250	1.00 TON	700-7000 AGRICULTURAL LIME		
255	50.00 TON	700-8000 FERTILIZER MIXED GRADE		
260	50.00 LB	700-8100 FERTILIZER NITROGEN CONTENT		
265	1,500.00 SY	702-0724 FESCUE SOD		
270	95.00 SY	716-2000 EROSION CONTROL MATS, SLOPES		
275	6.00 EA	938-1100 INTERSECTION VIDEO DETECTION SYSTEM ASSY, TYPE A		
TOTAL			ROADWAY	

1.23

ADDENDUM NO. 1

Cobb County Program Management Information System

Department of Transportation

Bid Schedule of Items - Project Detail

4/10/2012 10:24:34AM

Page 7 of 7

Contract No: C 000543

Vendor: _____

Project No: E804 SOPE CREEK ELEMENTARY PAPER MILL ROAD

Signature: _____

Group:W01 WATER

Line No.	Approx Quant.	Item	Unit Price	Amount
280	1.00 EA	660-C494 ADJUST EXISTING MH TO GRADE IN PAVEMENT 0-1 FT.		
285	5.00 EA	672-C155 ADJUST EXISTING VALVE BOX TO GRADE IN PAVEMENT		
290	1.00 EA	672-C156 ADJUST EXISTING VALVE BOX TO GRADE OUT OF PAVEMENT		
295	1.00 LS	674-C031 UTILITY ALLOWANCE	FIXED	\$5,000.00

TOTAL WATER

TOTAL MISCELLANEOUS

TOTAL RETAINING WALL #1

TOTAL ROADWAY

GRAND TOTAL E8040

FINAL PAGE

ADDENDUM NO. 1